

4-041594

8-2

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-167-21,214-0000

E2 SE NW /4 SEC. 22, 11 S, 15 W
1980 feet from N section line
2110 feet from W section line

Operator license# 5184 Lease Reich "B" well # 2

Operator: Shields Oil Producers, Inc. County Russell

Address: Shields Building Well total depth 3285 feet
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 258 feet
w/160 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 2 Month: August Year: 94

Plugging proposal received from: Marvin Ratts

Company: Shields Oil Producers, Inc. Phone: 913-483-3141

Were: 4 1/2" casing set @ 3281' w/75 sxs. cement. Perf. @ 3200' - 3250'. Anhy. @ 900' - Dakota @ 300' - W.L.M. 3250' - T.O.F. @ 1800'. Squeeze at 1060' w/250 sxs. cement. Ordered 175 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 2, Month: August, Year: 94

Actual plugging report: R.I.H. with tubing to 3200'. Spot 50 sxs. cement w/200# hulls. Pulled to 1500' - spotted 25 sxs. cement. Pulled to 880' perf. anhy. at 900': Pumped 60 sxs. cement with 100# hulls to circulate at surface. Pulled tubing and squeezed 4 1/2" casing to 1000# P.S.I. with 5 sxs. cement. 8 5/8" S.P. - pumped in 25 sxs. cement with 100# hulls. Max. 400#.

STATE CORPORATION COMMISSION

AUG 1 1 1994

Remarks: Blew hole in S.P. below ground level at 400#.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

CONSERVATION DIVISION
WICHITA, KANSAS

I did X] did not] observe the plugging.

Dennis L. Hamel

(agent)
Form CP-2/3

INVOICED

DATE 8-26-94

41041