

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23206-00-00 <sup>RT KCC</sup>  
Spot: CSWSWSW Sec/Twnshp/Rge: 28-11S-15W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: EULERT RANCH C Well Number: 3  
County: RUSSELL Total Vertical Depth: 3398 feet

Operator License No.: 6194  
Op Name: E S P DEVELOPMENT, INC.  
Address: 17746 177TH BOULEVARD  
PARADISE, KS 67658

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 200  
Production: Size \_\_\_\_\_ feet:  
Liner: Size \_\_\_\_\_ feet:

8110.44

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/28/2001 12:30 PM  
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC  
Proposal Rcvd. from: DOUG BUDIG Company: VONFELDT DRILLING, INC Phone: (785) 483-6446

Proposed Plugging Method: Order 175 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES  
Date/Time Plugging Completed: 09/28/2001 3:00 PM

Witness Type: Plugging Operations Were Not Witnessed  
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3280' w/25 sxs. Arbuckle 3292'.  
2nd. Plug at 940' w/25 sxs. Anhydrite 915' - 946'.  
3rd. Plug at 450' w/60 sxs.  
4th. Plug at 250' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED

NOV 05 2001

KCC WICHITA

INVOICED

DATE

11-5-01

WV. NO.

2002060906

NOV 01 2001