

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21148-00-00
Spot: W2W2E2 Sec/Twnshp/Rge: 22-11S-15W
^{8546 RTCC}
2640 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: REICH D Well Number: 3
County: RUSSELL Total Vertical Depth: 3271 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 MAIN
RUSSELL, KS 67665

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 250 160 sx cmt
Production: Size 4.5 feet: 3268 100 sx cmt
Liner: Size feet: 106.31

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/20/2001 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 230 sxs 60/40 pozmix - 10% gel - 500# hulls.
Tubing stuck in the hole at 771'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/20/2001 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto annulus and pumped to pressure with 15 sxs.
Max. P.S.I. 300#.
RIH with tubing to 700'
Tied onto tubing and circulated cement with 50 sxs and 300# hulls.
POOH. Hooked up to 4 1/2" and topped with 115 sxs.
Max. P.S.I. 400#. S.I.P. 150#.

RECEIVED

SEP 04 2001
09-04-01
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 9-4-01

INV. NO. 2002060322

Form CP-2/3

AUG 28 2001

SHIELDS OIL PRODUCERS, INC.
SHIELDS BLDG., RUSSELL, KS.

#3 REICH "D"

22-11-15W
APPX W/2 W/2 F/2

CONTR SHIELDS DRLG. CO., INC. CTY RUSSELL

GEOL MARVIN RATTS FIELD DREHER

E 1803 KB CM 2/17/77 CARD ISSUED 4/13/78 IP P 25 BOPD, NW
ARB OH 3268-71

API 15-167-21,148

	+	+
	+	+
-	+	+

SMP	TOPS	DEPTH	DATUM
ANH	869	+ 934	
B ANH	903	+ 900	
HEEB	2886	-1083	
TOR	2906	-1103	
LKC	2936	-1133	
ARB	3262	-1459	
RTD	3271	-1468	

8-5/8" 250/160sx, 4 1/2" 3268/100sx
DST (1) 3088-3160/30-30-30-30, 50'M,
SIP 125-125#, FP 102-114#
DST (2) 3248-67/30-30-30-30, 15'M,
SIP 841# - NO FSIP, FP 68-80#
DST (3) 3248-71/30-30-30-30, 140'
MDY 0, 240' HOCM, SIP 682-614#,
FP 91-182#
MICT - CO (ARB OH) AC 500, SWB DWN &
REC LD, POP