

To: 1 090189 4-23
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,850-0000 256
W/2 SW SE, SEC. 16, T. 34 S, R. 20 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3882

660 feet from S section line

2310 feet from E section line

Lease Name Selzer Well # 16-15

Operator: Samuel Gary, Jr. & Associates, Inc. County Comanche

Name & Address 1775 Sherman St., Ste. 1925

Well Total Depth 6500 all 25 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 687

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Brandt Drilling Co. License Number 5040

Address 200 W. Douglas, Ste. 700, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 23 Month: 4 Year: 19 92

Plugging proposal received from Merlin Freeman

(company name) Brandt Drilling Co. (phone) 316-267-4335

was: to fill hole with heavy mud and spot cement through drill pipe. Anhydrite 850'

1st plug at Arbuckle with 40 sx cement, 2nd plug at 850' with 50 sx cement,

3rd plug at 700' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:45 a.m. Day: 23 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 6410' with 40 sx cement,

2nd plug at 850' with 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form)

I did not observe this plugging.

INVOICED
DATE 5-14-92
INV. NO. 35241

Signed [Signature]
(TECHNICIAN)

RECEIVED
MAY 1 1992
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas