

1041323

TO: STATE CORPORATION COMMISSION

10-21

API NUMBER 15-033-20,870-0000
SE NW SEC. 16, T 34 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 2300 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2160 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SELZER WELL # 16-10

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE 200.20

OPERATOR LICENSE # 3882

WELL TOTAL DEPTH 6160' FEET

OPERATOR: SAMUEL GARY JR. & ASSOC.

PRODUCTION CSG: SIZE 5 1/2" @ 6160' WITH 700 SX

NAME AND 1670 BROADWAY SUITE 3300

SURFACE CASING: SIZE 8 5/8" @ 685' WITH 350 SX

ADDRESS DENVER, CO 80202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS 107 W FOWLER, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 21 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

10-27-98

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS: VIOLA @ 5959-72, 5978-90, 5903-08, 5910-14, 5919-34, 5940-53. CIBP @ 5890.

STAGE TOOL @ 5497. CMT RETAINERS @ 4573. LKC PERFS @ 4314-30.

1ST PLUG SET CIBP AT 4250' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH BAILER. PUMP DOWN

8 5/8" WITH 300# HULLS, 10S X GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS AND 150 SX CEMENT.

MAXIMUM PSI PRESSURE @ 500#. SHUT IN @ 400#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 21 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 4250' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH BAILER. PUMPED DOWN

8 5/8" WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS AND 150 SX CEMENT.

MAXIMUM PSI PRESSURE @ 550#. SHUT IN @ 400#.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3100' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

Signature of Stephen J Pfeifer (TECHNICIAN) and circular stamp

FORM CP-2/3

10-28-98

100214