

1091012

TO: STATE CORPORATION COMMISSION

9-23

API NUMBER 15-033-20,863-02
NW SE SE NW SEC. 16, T 34 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 2300 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2110 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME SELZER WELL # 16-8

TECHNICIAN'S PLUGGING REPORT COUNTY COMANCHE

OPERATOR LICENSE # 3882 WELL TOTAL DEPTH 6600 214.50 FEET

OPERATOR: SAMUEL GARY JR & ASSOC. PRODUCTION CSG: SIZE 5 1/2" @ 6600' WITH 740 SX

NAME AND ADDRESS 1670 BROADWAY, SUITE 3300 SURFACE CASING: SIZE 8 5/8" @ 687' WITH 325 SX

DENVER, CO 80202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 2:45 PM DAY: 23 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TOM LARSON

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 6488-94

SET CIBP @ 4240' WITH 2 SX CEMENT ON TOP. PUMP DOWN 8 5/8" CASING 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:45 PM DAY: 23 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT

SET CIBP AT 6460' WITH 2 SX CEMENT ON TOP. ALSO SET CIBP AT 4240' WITH 2 SX CEMENT.

SWIFT PUMPED DOWN 8 5/8" CASING WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 5 SX GEL - 8 5/8" WIPER PLUG - 150 SX CEMENT.

MAXIMUM PRESSURE AT 800#. SHUT IN WITH 700#.

INVOICED

DATE 10-8-99

INV. NO. 20000100663

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT. RECOVERED 3500' OF 5 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM SEP 29 1999 9-21-99)

I (DID) OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) CONSERVATION DIVISION FORM CP-2/3

Handwritten signature and initials.