

1041320

TO: STATE CORPORATION COMMISSION 10-21

API NUMBER 15-033-20,885 - 0000
NW NW SEC. 15, T 34 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BOB WHITE WELL # 15-1

TECHNICIAN'S PLUGGING REPORT COUNTY COMANCHE 2425 214.50

OPERATOR LICENSE # 3882 WELL TOTAL DEPTH 6600' FEET

OPERATOR: SAMUEL GARY JR. & ASSOC. PRODUCTION CSG: SIZE 5 1/2" @ 6251' WITH 125 SX

NAME AND 1670 BROADWAY SUITE 3300 SURFACE CASING: SIZE 8 5/8" @ 721' WITH 375 SX

ADDRESS DENVER, CO 80202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS 107 W FOWLER, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 10:15 AM DAY: 21 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL 10-27-98

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS: 6083-6091 CIBP @ 6106'

1ST PLUG SET CIBP AT 5700' AND PUT 2 SX CEMENT ON TOP OF CIBP WITH BAILER. PUMP DOWN 8%

WITH 300# HULLS 10SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS 8 5/8" WIPER PLUG AND 150 SX

CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00 AM DAY: 21 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 5700' AND PUT 2 SX CEMENT ON TOP OF CIBP WITH BAILER. PUMPED DOWN 8%

WITH 300# HULLS, 10 SX GEL, 50S X CEMENT, 10 SX GEL, 100# HULLS, 8 5/8" WIPER PLUG AND 150 SX

CEMENT. MAXIMUM PSI PRESSURE @ 600#. SHUT IN @ 400#.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3831.46' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CP-23

10-28-98
60212