

12-28

To: 6 041124  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 167-01,704-0000  
NE NW SW, SEC. 9, T 11 S, R 15 W/E

TECHNICIAN'S PLUGGING REPORT

2310 feet from S section line  
4290 feet from E section line

Operator License # 6854

Lease Name Chrisler B Well # 1  
County Russell 112.35

Operator: B. P. Exp Inc.  
Name & Address Box 37  
Gorham, Ks. 67640

Well Total Depth 3457 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 13 3/8 feet 145' w/13 sk

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Cementing License Number \_\_\_\_\_

Address Hays, Ks.

Company to plug at: Hour: 9:00AM Day: 28 Month: Dec Year: 19 89

Plugging proposal received from Joel Stull

(company name) B. P. Exp (phone) \_\_\_\_\_

were: 5 1/2" casing set at 3414' w/125 sks. Top pf the tubing fish at 3177':

Perf at 3106' - 3297': C.I.B.P. at 3390' w/1 sks cement. Perf casing at 900' and  
perf at 150 (sq at 580' w/50 sks - 1954) (Sq at 755' w/100 sks - 1982)

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30PM Day: 28 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Set EZSV at 3000': Sq 100 sks cement w/3 sks hulls

at 500# s.i: Stung out and circ 25 sks cement to 2700' : Circ 10 sks gel to 900'  
Spotted 75 sks cement to circ cement to surf: pulled tubing: sq add 50 sks out perfs  
at 900' and 150#: Perf casing at 150' base of s.p. and sq add 125 sks cement to circ  
annulus: Shut in annulus and pressured up to 50# psi.

RECEIVED  
STATE CORPORATION COMMISSION

1-17-90  
JAN 17 1990

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

Signed Dennis L. Hamel  
Dennis L. Hamel  
TECHNICIAN

CONSERVATION DIVISION  
Wichita, Kansas

DATE JAN 24 1990  
INV. NO. 27087