

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy) -0000

API NUMBER 15-167-01705 Drilled April 1963 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR BP Exploration Inc. OPERATORS LICENSE NO. 06854
ADDRESS P.O. Box 4587 Houston, Tx. 77210 PHONE # (713) 552-8500

LEASE (FARM) Chrisler B WELL NO. 2 WELL LOCATION NE NE SW COUNTY Russell
SEC. 9 TWP. 11S RGE. 15 ~~XX~~ or (W) TOTAL DEPTH 3465' PLUG BACK TD 3346'

Check One:

OIL WELL XXX GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 10 3/4" SET AT 101' CEMENTED WITH 100 SACKS
CASING SIZE 7" SET AT 3453' CEMENTED WITH 150 SACKS
PERFORATED AT 3092-3316' L-KC Block squeeze @ 1060' w/ 400 sx cement
TOC: surface

CONDITION OF WELL: GOOD XXXX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1) Set retainer at 3000', squeeze perforations with 100+ sx 65-35 Pozmix; 2) spot 15 sx of Pozmix on top of retainer; 3) spot 200' cement plug; 30 sx, from 900-1100' to cover anhydrite; 4) spot 100' surface plug, 15 sx Pozmix;
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Nov. 21, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION. 11-13-89

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Joel Stull - field supervisor PHONE # (913) 637-5290
ADDRESS Gorham, Ks. 67640

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 5287
ADDRESS 1100 East 8th St. Hays, Ks. 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Joanne Chesko
(Operator or Agent)

DATE: 11-10-89

4

5) Cut casing below plow depth and weld on steel plate.

Note: 1) 9.0 ppg mud (36 cp viscosity) will be placed between all cement plugs.
2) Cement exists across the anhydrite behind the 7" casing.



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

THIS NOTICE
FEB 13 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

November 13, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

BP Exploration, Inc.
P.O. Box 4587
Houston, TX 77210

Chrisler B 2
NE NE SW
09-11-15W
Russell County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200