

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 033-98020 ¹⁹⁰⁰¹⁻ ~~0000~~ (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date May 1971

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334

Address: P.O. Box 18496 City: Oklahoma City

State: Oklahoma Zip Code: 73154-0496 Contact Phone: (405) 935 - 3906

Lease: Pyle A Well #: 2 Sec. 13 Twp. 31 S. R. 18 East West

 - NW - NW - SW Spot Location / QQQQ County: Comanche

2180 2067 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

5130 5/26 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # 16057 ENHR Docket # Other:

Conductor Casing Size: Set at: Cemented with: Sacks

Surface Casing Size: 8 5/8" Set at: 505 Cemented with: 200 Sacks

Production Casing Size: 5 1/2" Set at: 1,002 Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: Cedar Hills 710-746, Packer set at 652'

Elevation: (G.L. / K.B.) T.D.: 1,008 PBDT: 971 Anhydrite Depth: 994'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):
See Attached Procedure

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 16 2010

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

CONSERVATION DIVISION
WICHITA, KS

If not explain why? Injection well, no logs available.

Plugging of this Well will be done in accordance with K.S.A. 55-101' et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations:

Bud Neff, Production Superintendent Phone: (620) 277 - 0803 ext. 11

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99986

Address: P.O. Box 31, Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?):

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6-14-10 Authorized Operator / Agent:

David Wiist

Digitally signed by David Wiist
DN: dc=net, dc=chkenergy, ou=Users
and Groups, cn=David Wiist,
email=david.wiist@chk.com
Date: 2010.06.14 14:46:29 -05'00'

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Pyle A 2(SWD)
P&A
5-28-10

Procedure

1. Notify KCC District 1 at least 5 days before plugging operations
KCC District 1: (620)225-8888
2. MIRU WOR, release packer, TOOH with 2 3/8" tubing.
3. PU 5 1/2" CIBP, TIH with plug and set at $\pm 660'$. Dump 2 sx cement w/2% CaCl_2 on top of CIBP (Plug 1). TOOH w/tubing while circulating plugging mud.
4. TIH with tubing, pump the following plugs in casing displacing with plugging mud:

Plug 2: Shoe plug (610'-460')	20 sx. w/ 2% CaCl_2
Plug 3: Fresh water plug (250'-100')	20 sx w/ 2% CaCl_2
Plug 4: Surface plug (34'-4')	4 sx. w/ 2% CaCl_2
5. Cut off casing 4ft. below ground level, weld on steel ID plate. RDMO WOR.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 16 2010

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman, Joseph F. Harkins, Commissioner, Ward Loyd, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

CHESAPEAKE OPERATING, INC.
6200 N WESTERN AVE
PO BOX 18496
OKLAHOMA CITY, OK 73118-1046

June 18, 2010

Re: PYLE A #2
API 15-033-19001-00-00
13-31S-18W, 2067 FSL 5126 FEL
COMANCHE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after December 15, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888