

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6445
Name: Miller Brothers Oil Co. Inc
Address 1: 701 west 4th
Address 2: _____
City: Lebo State: Ks. Zip: 66856 + _____
Contact Person: Don Miller
Phone: (620) 256-0108

API No. 15 - 207-20436-0000
If pre 1967, supply original completion date: _____
Spot Description: _____
SE NW SW Sec. 23 Twp. 23 S. R. 13 ☒ East ☐ West
1,890 Feet from ☐ North / ☒ South Line of Section
835 Feet from ☐ East / ☒ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☐ SE ☒ SW
County: Woodson
Lease Name: A J Hessler Well #: 19

Check One: ☒ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic ☐ Water Supply Well ☐ Other: _____
☐ SWD Permit #: _____ ☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 7 in. Set at: 107 Cemented with: 50 Sacks
Production Casing Size: 4.5 Set at: 2190 Cemented with: 100 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Bridge Plug 1785' Perf-2140-2144 : 1776-1782 : 1750-1754 : 1744-1748
Bridge Plug 1724' Perf- 1699-1708

Elevation: 1210 est (☒ G.L. / ☐ K.B.) T.D.: 2190 PBDT: 2176 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: ☐ Good ☒ Poor ☐ Junk in Hole ☐ Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Pull all of the 4.5 casing we can. Run 2inch back down to 1700' pump 20 sacks cement. Come up to below the Douglas set 10 sks. come up above the Douglas set 10 sks. Come up and fill from 200' to surface.

Is Well Log attached to this application? ☒ Yes ☐ No Is ACO-1 filed? ☐ Yes ☐ No

If ACO-1 not filed, explain why:

Miller Brothers Oil Co. Inc. did not own this lease when this well was drilled and have no record if the ACO-1 was filed or not.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Daniel Horst
Address: 1707 Yucca Lane City: Emporia State: Ks. Zip: 66801 + _____
Phone: (620) 344-1518
Plugging Contractor License #: 7719 Name: Cheever Well Service
Address 1: Box 677 Address 2: _____
City: Madison State: Ks. Zip: 66860 + _____
Phone: (620) 437-2296
Proposed Date of Plugging (if known): June 16/10

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6-11-10 Authorized Operator / Agent: Daniel Horst (Signature)

RECEIVED
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

JUN 15 2010

CONSERVATION DIVISION
WICHITA, KS



Mark Parkinson, Governor Thomas E. Wright, Chairman, Joseph F. Harkins, Commissioner, Ward Loyd, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

MILLER BROS. OIL COMPANY, INC.
701 W 4TH
LEBO, KS 66856

June 28, 2010

Re: AJ HESSLER #19
API 15-207-20436-00-00
23-23S-13E, 1890 FSL 835 FWL
WOODSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after December 25, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely

Steve Bond
Production Department Supervisor

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300