

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22323-00-00
Spot: W2NENWSW Sec/Twnshp/Rge: 22-29S-15W
2310 feet from S Section Line, 860 feet from W Section Line
Lease Name: HIRT "C" Well #: 1
County: PRATT Total Vertical Depth: 4890 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4700		WITH 2 SX CMT
CIBP		4767		
SURF	10.75	277		WITH 225 SX CMT
PROD	5.5	4872	3018	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/26/2010 10:00 AM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (620) 546-4801

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. SPOT 15 SX GEL & 50 SX CMT @ 1000'. SPOT 75 SX CMT AT 300'. SPOT 25 SX CMT AT 40'.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/26/2010 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4700' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. TOPPED OFF WITH 75 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4774	4778		SIMPSON SAND
4727	4734		SIMPSON DOLOMI

INVOICED
DATE 6/22/10
INV. NO. 2010061272

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 21 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

JUN - 8 2010

KCC DODGE CITY

FORM CP-2/3