

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10694-00-01
Spot: NESWNW Sec/Twnshp/Rge: 32-26S-12W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: MISKIMAN V E Well #: 4
County: PRATT Total Vertical Depth: 4310 feet

Operator License No.: 9232
Op Name: TIMBERLINE OIL & GAS CORPORATIO
Address: 4000 PENROSE PL
RAPID CITY, SD 57702

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	423		WITH 200 SX CMT
PROD	5.5	4310	2000	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/03/2010 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SPOT 200# HULLS & 30 SX CMT. PLUG AT 750' WITH 15 SX GEL & 50 SX CMT. PLUG AT 442' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/03/2010 11:10 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

RUN TBG TO 3815' & SPOT 200# HULLS & 30 SX CMT. LET CMT SET. TAG TOC @ 3638'. 1ST PLUG AT 750' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 442' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4232	4241		
4222	4230		
4208	4222		
4205	4208		
3932	3942		
3841	3846		

INVOICED

6/22/10

NO. 2010061275

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 21 2010


CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIZ 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED

JUN - 8 2010

KCC DODGE CITY

Form CP-33