

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23031-00-01
Spot: SENWSENE Sec/Twnshp/Rge: 35-27S-4E
3320 feet from S Section Line, 734 feet from E Section Line
Lease Name: SKAER A Well #: 22
County: BUTLER Total Vertical Depth: 2660 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2138		
SURF	8.625	253		150 SX
PROD	5.5	2659		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2010 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: _____ Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 06/07/2010 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2,030', CONSOLIDATED WELL SERVICES MIXED & PUMPED 75 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. TAGGED CEMENT @ 1,275'. LOADED HOLE & PRESSURED CASING @ 500#, BLED OFF SLOWLY. WAITED 1 HOUR, RE-TAGGED CEMENT SOLID @ 1,675'. PRESSURED BACKSIDE @ 400#, PRESSURED INSTANTLY. SWEDGED INTO 5-1/2" CASING, CONSOLIDATED MIXED & PUMPED 60 SXS CLASS A COMMON. SHUT IN PRESSURE 800#. PLUG DOWN 12:00 P.M., 6-7-2010. CONSOLIDATED OIL WELL SERVICES TICKET #28292.

Perfs:

Top	Bot	Thru	Comments
2599	2602		ARBUCKLE
2583	2588		ARBUCKLE-SQZ
2554	2560		SIMPSON-SQZ
2057	2067	CSG	
2036	2042	CSG	

INVOICED
DATE 6/22/10
INV. NO. 2010061276

Remarks: SQUEEZED CASING LEAKS @ 960'-990' W/200 SXS, & 1,421'-1,452' W/225 SXS

Plugged through: TBG

District: 02

RECEIVED
KANSAS CORPORATION COMMISSION

John Klock

(TECHNICIAN)

JUN 21 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3