

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19801-00-00
Spot: N2S2S2N2 Sec/Twnshp/Rge: 28-30S-16E
3094 feet from S Section Line, 2640 feet from E Section Line
Lease Name: KEYS HEIRS Well #: 7
County: WILSON Total Vertical Depth: 828 feet

Operator License No.: 3830

Op Name: A X & P, INC.

Address: PO BOX 1176
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	5	700		
PROD	2	800		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/08/2009 8:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: J J HANKE

Company: AX&P, INC

Phone: (620) 920-0078

Proposed
Plugging
Method:

Remove 2" production casing and fill from btm to top thru cement string.

Plugging Proposal Received By: ALAN DUNNING

Witness Type: NONE

Date/Time Plugging Completed: 12/19/2009 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The 2" production casing could not be removed. Therefore, the well was perforated at 650', 250' and 50'. A 1" cement string was washed to 800' and the well pumped full of cement. A total of 150 sacks of portland cement were used to plug well.

RECEIVED

JUN 18 2010 AMD

KCC Chanute Dist. #3

INVOICED
DATE 6/22/10
INV. NO. 2010061277

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 22 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3