

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02365-00-00
Spot: NESENW Sec/Twnshp/Rge: 15-19S-10W
3596 feet from S Section Line, 2979 feet from E Section Line
Lease Name: FELDMAN Well #: 4
County: RICE Total Vertical Depth: 3291 feet

Operator License No.: 33725
Op Name: FOUNDATION ENERGY MANAGEMEN
Address: 14800 LANDMARK BLVD STE 220
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3238		
SURF	8.625	184		115 SX
PROD	5.5	3288		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2010 9:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: KENT STRUBE Company: FOUNDATION ENERGY MGMT LL Phone: (620) 786-4161

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 05/24/2010 11:50 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1200', 850', AND 250'. RUN TUBING TO 3180' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 1200' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 850' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. CLOSED VALVE ON 5.5" AND ATTEMPT CIRCULATING CEMENT OUT OF SURFACE CASING -- GOT COLORED RETURNS. PUMPED CEMENT DOWN BACKSIDE OF 5.5" UP TO 200#"S. PULL TUBING OUT AND TOP OFF. USED 345 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3288	3291	OH	ARBUCKLE
2962	3156	CSG	LANSING
2838	2866	CSG	DOUGLAS

INVOICED
DATE 6/22/10
INV. NO. 2010061278

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 22 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL EXCEPT WHERE OTHERWISE SPECIFIED. COPELAND TICKET C-37057. GRESSELL PERF TICKET #719.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)