

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-04435-00-00
Spot: SWNENW Sec/Twnshp/Rge: 15-19S-10W
4246 feet from S Section Line, 3624 feet from E Section Line
Lease Name: FELDMAN Well #: 6
County: RICE Total Vertical Depth: 3210 feet

Operator License No.: 33725
Op Name: FOUNDATION ENERGY MANAGEMEN
Address: 14800 LANDMARK BLVD STE 220
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2914		
SURF	8.625	204		
PROD	4.5	3196		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/25/2010 9:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: KENT STRUBE Company: FOUNDATION ENERGY MANAGE Phone: (620) 786-4161

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 05/25/2010 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1200', 850', AND 250'. RUN TUBING TO 2900' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 1200' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 850' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 255 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3043	3167	CSG	
2862	2872	CSG	

INVOICED

DATE 6/22/10

NV. NO. 2010061278

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 22 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL UNLESS OTHERWISE SPECIFIED. GRESSEL PERF TICKET 720. COPELAND TICKET #C-37058.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)