

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25420-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 22-18S-11W
1640 feet from N Section Line, 2310 feet from E Section Line
Lease Name: KAISER Well #: 2
County: BARTON Total Vertical Depth: 3354 feet

Operator License No.: 3941
Op Name: LOGAN, LESLIE DBA L. B. OIL
Address: 211 8TH ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	324		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/13/2010 2:00 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: JAY Company: L.B. OIL Phone: (620) 587-3511

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT BEDORE WitnessType: NONE
Date/Time Plugging Completed: 06/13/2010 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

1st. Plug at 3297' w/25 sxs.
2nd. Plug at 570' w/25 sxs.
3rd. Plug at 320' w/80 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

INVOICED
DATE 6/28/10
INV. NO. 2010061287

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

JUN 25 2010

Form CP-2/3

KCC WICHITA

JUN 14 2010