

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24534-00-00
Spot: NENESW Sec/Twnshp/Rge: 21-13S-20W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SCHUMACHER Well #: 1
County: ELLIS Total Vertical Depth: 3846 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	232	0	140 SX
PROD	4.5	3839	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2010 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Alt II. DV at 1619' w/400 sxs.
Low fluid level.
Operator elected all cement plug.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/18/2010 10:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to 4 1/2" casing with a swedge and pumped 225 sxs cement with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
Rigged to 8 5/8" casing and pumped 1/4 sack - instant pressure.

Perfs:

Top	Bot	Thru	Comments
3826	3828		CONGLOMERATE


INVOICED
DATE 6/28/10
INV. NO. 2010061289

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4044.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

JUN 25 2010

Form CP-2/3

KCC WICHITA

JUN 23 2010

CARMEN SCHMITT, INC
BELOIT, KS 67420

21-13 -20W
NE NE SW

#1 SCHUMACHER

site: 1-1/2 S OF ELLIS, KS
contr: RED TIGER DRILLING COMPANY
geol: RICHARD O'DONNELL

cty: ELLIS
field: PLEASANT NW

API 15-051-24534

fr date 11/05/87 spd date 11/06/87 drig comp 11/13/87 card issued 02/17/88 last revised 02/17/88

ELV: 2212 KB LOG	
tops.....	depth/datum
ANH.....	1541 +671
TOP.....	3227 -1015
HEEB.....	3462 -1250
TOR.....	3480 -1268
LANS.....	3500 -1288
BKC.....	3747 -1535
MARM.....	3788 -1576
CONG.....	3824 -1612
RTD.....	3846 -1634

IP status:
OIL, P 30 BO & 73 BWP, CONG 3837-3846 , (NEW PAY)
 ,
 CSG: 8-5/8" 232.15 / 140 SX, 4-1/2" 3839 / 600 SX
 NO CORES
 DST (1) 3664-3698 (LKC), / 45-30-45-30, REC 200' MW
 ISIP 789# FSIP 758# IFP 51# -103# FFP 72# -103# IHP
 1921# FHP 1869#

(over)

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

CARMEN SCHMITT, INC
BELOIT, KS 67420

21-13 -20W
NE NE SW

#1 SCHUMACHER

DST (2) 3721-3748 (LKC), / 30-30-5-0, REC 5' M, NSO ISIP 31# IFP 31# -31# FFP 31# -31#
 IHP 2025# FHP 1869#
 DST (3) 3811-3846 (CONG), / 30-30-30-30, 765' GIP, REC 1054' CLEAN GSY OIL, 180' MCO
 ISIP 957# FSIP 862# IFP 163# -374# FFP 418# -495# IHP 2073# FHP 2062#
 MICT - CO, PF (CONG) 3837-3845, W / 4 SPF, AC 600 GAL, GSO, SET 2-3/8" TBG AT 3834.53,
 POP, P 30 BO & 73 BWP, 1/1/88