

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21530-00-00
Spot: NENWNE Sec/Twnshp/Rge: 32-7S-19W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SCHOELLER Well #: 2
County: ROOKS Total Vertical Depth: 3405 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	328	0	250 SX
PROD	4.5	3397	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/16/2010 9:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 885-8240

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 1000# hulls.
Holes in the casing at approximately 1000' to 1100'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/16/2010 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3358' - pumped 50 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled tubing to 2600' - pumped 70 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1600' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1000' - pumped 80 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Hooked to 4 1/2" casing - pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 250#.
Hooked to 8 5/8" x 4 1/2" annulus.
Pumped 10 sxs 60/40 pozmix - 4% gel.
S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3305	3310		
3287	3294		
3266	3271		
3136	3144		

INVOICED
DATE: 6/28/10
INV NO: 20100612 0

Remarks: ALLIED CEMENTING COMPANY-TICKET #41631.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

JUN 25 2010

Form CP-2/3

KCC WICHITA

JUN 22 2010

THUNDERBIRD DRLG INC &
 PARAGON PETRO CORP
 P.O. BOX 18407
 WICHITA, KS 67207
 CONTR COMPANY TOOLS

#2 SCHOELLER
 CTY ROOKS

32-7-19W
 NE NW NE

GEOL _____ FIELD RESERVOIR

E 1952 KB CM 1/3/82 CARD ISSUED 3/4/82 IP P 55 BOPD, NW

+	+	+	+
+	+	+	+
+	+	+	+

API 15-163-21,530

LANS 3136-3310 OA

LOG	TOPS	DEPTH	DATUM
ANH		1416	+ 536
TOP		2904	- 952
HEEB		3098	-1146
LANS		3136	-1184
BKC		3350	-1398
ARB		3388	-1436
LTD		3401	-1449
RTD		3405	-1453

8-5/8" 328/250sx; 4 1/2" 3397/125sx

DST (1) 3125-3150/30-60-45-90,
 120' GIP, REC 10' FO, 20' OCM,
 SIP 464-592#, FP 29-29#

DST (2) 3166-3205/30-60-30-60,
 60' GIP, REC 90' W W/SO, SIP
 925-853#, FP 55-66#

DST (3) 3205-3240/30-60-30-60,
 120' GIP, REC 200' MW, SIP 1178-
 1120#, FP 59-128#

DST (4) 3260-3290/30-60-30-60, 1090'
 GIP, REC 180' CL GO, 410' GCOM, SIP
 807-454#, FP 79-237#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)

THUNDERBIRD DRLG INC &
 PARAGON PETRO CORP

#2 SCHOELLER

32-7-19W
 NE NW NE

DST (5) 3284-3325/30-60-30-60, 120'
 GIP, REC 200' O, 240' HOCM, SIP
 886-866#, FP 79-197#

DST (6) 3225-3360/30-60-30-60, 120'
 GIP, REC 2' O SPKD M, SIP 1071-
 1003#, FP 39-39#

MICT - CO, PF 3305-3310, SWB DWN, AC

250G, SWB LD & TST 4.18 BF, 23% W/30", AC 1000G, SWB LD,
 1500' FIH, SWB DWN & TST 25 BO, NW, SWB 5 BO/20", PF 3287-

3294, RBP AT 3300', TST 5.85 BO/20" COMMUNICATED W/PF
 3305-3310, PULL PLUG, PF 3266-3271, BP AT 3279, TST 2.51
 BF/30", TR WTR, TST 11.10 BF/1 HR, 50% W, 2.51 BF/15" -

15% WTR, AC 250G, SWB PT LD, 1200' FIH, REC 19 BF (12 BO +
 7 BW), PULL PLUG, PF 3136-3144, BP 3160', SWB LD, TST

.42 BO DECR TO 10 GOPH, AC 250G, SWB SHOW OIL, REC PT LD,
 AC 1000G, SWB .84 BF/1ST HR, 10% W, SWB .84 BF/2ND HR, AC
 1000G, SWB LD, SWB 6.68 BOPH, PULL PLUG AT 3160', R&T,
 POP, P 55 BOPD, 2/18/82