

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-21846-00-00  
Spot: N2SWNWSE Sec/Twnshp/Rge: 21-14S-31W  
1800 feet from S Section Line, 2250 feet from E Section Line  
Lease Name: THIES RANCH Well #: 1-21  
County: GOVE Total Vertical Depth: 4580 feet

\$ 148.85

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/19/2010 3:00 PM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Rcvd. from: LARRY HINDERSHOT Company: LARIO OIL & GAS COMPANY Phone: (316) 265-5611

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE  
Date/Time Plugging Completed: 06/19/2010 4:30 PM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 2260' w/25 sxs.  
2nd. Plug at 1300' w/100 sxs.  
3rd. Plug at 270' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:


INVOICED  
DATE 6/30/10  
INV. NO. 2010061296

Remarks: CONSOLIDATED ACID AND CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED Form CP-2/3

JUN 28 2010

KCC WICHITA

JUN 24 2010