

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24422-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 19-20S-15W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: IANNITTI Well #: 4
County: BARTON Total Vertical Depth: 3881 feet

\$ 126.13

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1135	0	400 SX
PROD	5.5	3879	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/16/2010 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (620) 793-5838

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.
Set up to pull casing - sanded off perms - topped with 5 sxs cement.
Could not pull casing out of surface head - decided to not pull casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/16/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3725' - pumped 13 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1650' - pumped 90 sxs cement with 300# hulls.
Pulled tubing to 815' - pumped 12 sxs cement - circulated cement to surface on casing.
Closed valve on casing - pumped 56 sxs cement into backside.
Pressured to 800# P.S.I. - pulled tubing.
Tied onto casing and pumped 15 sxs cement.
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3825	3827		
3820	3822		
3815	3817		
3804	3807		

INVOICED
DATE 6/30/10
INV. NO. 2010061301

Remarks: ALLIED CEMENTING COMPANY-TICKET #36694.

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

RECEIVED

JUN 28 2010

JUN 23 2010

KCC WICHITA