

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24479-00-00  
Spot: E2SWNWSW Sec/Twnshp/Rge: 19-20S-15W  
1650 feet from S Section Line, 4750 feet from E Section Line  
Lease Name: IANNITTI Well #: 7  
County: BARTON Total Vertical Depth: 4000 feet

\$ 130.

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		
SURF	8.625	1110	0	400 SX
PROD	5.5	3999	0	250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2010 8:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (620) 793-5838

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.  
Set up to pull casing - sanded off perms - topped with 5 sxs cement.  
Could not pull casing out of surface head - decided to not pull casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/21/2010 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3700' - pumped 13 sxs gel - followed with 50 sxs cement and 200# hulls.  
Pulled tubing to 1650' - pumped 90 sxs cement with 300# hulls.  
Pulled tubing to 800' - pumped 87 sxs cement - circulated cement to surface on casing.  
Closed valve on casing - pumped 50 sxs cement into backside - circulated cement to surface - pulled tubing.  
Tied onto casing - pumped 12 sxs cement.  
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3822	3825		
3798	3802		
3792	3795		

INVOICED  
DATE 6/30/10  
INV. NO. 2010061301

Remarks: ALLIED CEMENTING COMPANY-TICKET #36699.

Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

RECEIVED Form CP-2/3

JUN 28 2010

KCC WICHITA

JUN 23 2010

**STATE:** KANSAS      **COUNTY:** BARTON      **19-20S-15W**  
**FIELD:** PAWNEE ROCK FLD(ARBUCKLE)      S2 NW SW  
**OPER:** IANNITTI OIL      1650 FSL 4700 FEL SEC  
**WELL:** 7 IANNITTI      **WELL CLASS:** DO      **ELEV:** 2088 KB  
**API:** 15-009-24479      **STATUS:** OIL      2083 GR  
**SPUD:** 06/07/91      **COMP:** 08/10/91  
**DTD:** 4000      **LTD:**      **FTD:** ARBUCKLE      **PBTD:** 3850

**LOC:** 3 MI NW PAWNEE ROCK, KS

**IP:** COMP 8/10/91, IPP 70 BO, 5 BWPD, GTY 35 **PROD ZONE-** ARBUCKLE 3792-3802  
 GROSS  
 NO CORES, FOUR DSTS

**LOG TOPS:**

ANHYDRITE	1102 986	DOUGLAS	3433 -1345
BSE ANHYDRITE	1122 966	LANSING-KANSAS CITY	3502 -1414
HEEBNER	3404 -1316	BSE LANSING-KANSAS CITY	3730 -1642
TORONTO	3422 -1334	ARBUCKLE	3789 -1701
TD	4000 -1912		

**LOG TYPES:** CDL, CNL, DILL, ML;

**CSGS:** 8 5/8 @ 1110 W/400 SX, 5 1/2 @ 3999 W/150 SX; DRLG COMP 06/14/91  
**DSTS:** **DST # 1** (ARBUCKLE) 3793-3799, (MISRUN) **DST # 2** (ARBUCKLE) 3793-3799, OP 30 MIN, SI 30 MIN, OP 30 MIN, SI 30 MIN, GAS TS 10 MIN 542

**(OVER)**

COPYRIGHT 1991 PETROLEUM INFORMATION CORPORATION

**DATE 10/18/91 CARD #00032-KS**