

126.20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21361-00-00
Spot: SENWNW Sec/Twnshp/Rge: 24-20S-16W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: OETKIN Well #: 5
County: PAWNEE Total Vertical Depth: 3883 feet

Operator License No.: 32278

Op Name: TENGASCO, INC.

Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1093		WITH 400 SX CMT
PROD	5.5	3882	1598	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2010 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DIXON Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5838

Proposed Plugging Method: SAND BOTTOM OFF & 2 SX CMT. PULL CASING. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2010 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 3670' WITH 2 SX CMT. 1ST PLUG AT 1116' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3812	3821		ARBUCKLE

INVOICED
DATE 6/30/10
INV. NO. 201006/301

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 30 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JUN 23 2010
KCC DODGE CITY