

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21648-00-00 9/150.96  
Spot: NWSENESE Sec/Twnshp/Rge: 5-22S-24W  
1764 feet from S Section Line, 335 feet from E Section Line  
Lease Name: BOGER Well #: 1-5  
County: HODGEMAN Total Vertical Depth: 4645 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String Size Depth (ft) Pulled (ft) Comment  
SURF 8.625 225 WITH 150 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2010 5:30 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 06/23/2010 7:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED  
DATE 6/30/10  
INV. NO. 2010061303

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

JUN 23 2010

KCC DODGE CITY

Signed

*Eric MacLaren*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CR-2/3

JUN 30 2010

CONSERVATION DIVISION  
WICHITA, KS