

To: 6 031310
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-5
API NUMBER 15- 167-22,883-0000
SE NW NW, SEC. 28, T. 11 S, R. 15 W/E
4290 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5135
Operator: John O. Farmer
Name & Address: Box 352
Russell, Ks. 67665

Lease Name Krug Well # B-1
County Russell 107.58
Well Total Depth 3310 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x
Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Oper License Number 8241
Address Russell, Ks.

Company to plug at: Hour: AM Day: 5 Month: Dec Year: 89
Plugging proposal received from Jack Fox

(company name) Emphasis (phone) _____

were: 8 5/8" set at 205' w/135 sks cwc circ hole w/no less than 36 vis mud
w/no loss or gain of fluid. Balance plugs w/mud, keep hole full.
Order 205 sks 60/40 poz 6% gel 3% cal cl Allied.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 12:00AM Day: 5 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 3271' w/25 sks
925' w/25 sks
500' w/90 sks
250' w/40 sks
40' w/10 sks

Remarks: Circ 15 sks in rathole w/pipe. Elev. 1825' Anhy 906' - 36' Arb top 3296

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED

DATE JAN 24 1990

INV. NO. 27122

John S

FEB 09 1990

Signed Carl Goodrow
(TECHNICIAN) Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1990
01-17-90

FORM CP-2/3
Rev. 01-84