

X 11-22 15-167-04548-0001
Booklet D-9234

6 070727

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE SW SE, SEC. 28, T 11 S, R 15 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5844

feet from S section line

feet from E section line

Operator: Don Widrig

Lease Name Hagaman Well # 4 SWD

Name & Address

County Russell 35.00

Well Total Depth 915 feet

Box 8
McPherson, Ks. 67460

Conductor Pipe: Size 0 feet

Surface Casing: Size 0 feet

Abandoned Oil Well Gas Well Input Well SWD Well x D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number

Address Box 31 Russell, Ks. 67530

Company to plug at: Hour: 11:00AM Day: 21 Month: Nov Year: 19 88

Plugging proposal received from Don Butcher and Don Widrig

(company name) KCC and Widrig Oil Co. (phone)

were: 4 1/2" casing set at 915' w/235 sks cement. 2 7/8" set at N.A. w/N.A. cement

(SWD) on good vacuum. Proposal 250 sks Class A Common Cement pump in 4 1/2" casing with pump truck load 4 1/2" casing with cement and shut in under pressure.

RECEIVED
STATE CORPORATION COMMISSION
12-29-88
DEC 29 1988

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN) Wichita, Kansas

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:09 Day: 22 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Ordered 250 sks Class A Common Cement w/3 sks F.C.

Pumped in 4 1/2" casing with pump truck.

1. On Nov 21, 1988 pumped in casing 250 sks cement w/2 sks Flocele SWD on vacuum.

2. Returned for another 200 sks 60/40 Poz 6% Gel 3% Cal Cl.

3. On Nov 21, 1988 pumped in another 200 sks cement w/2 sks Celloflake and 1 sk Hulls

still on vacuum. 4. On Nov 22, 1988 pumped in 15 sks cement. Max psig 350-casing

Remarks: ruptured at surface. Cemented by Allied Cement. Plug down at 11:09 A.M.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 1-9-89

INV. NO. 23536

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

Bruce Basye
Bruce D. Basye FORM CP-2/3
Rev. 01-84