

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-22, 070-00-00

SW, Sec. 36, T 13 S, R 11 W

1650 feet from S section line

2310 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Cowie A Well # 1

Operator: Thunderbird Drilling, Inc.
Name & Address P.O. Box 18407, Wichita, Ks. 67218

County Russell

Well Total Depth 3350 feet \$108.88

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 330

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Thunderbird Drilling, Inc. License Number 38

Address P.O. Box 18407, Wichita, Ks. 67218

Company to plug at: Hour: 4:00 PM Day: 23 Month: 2 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Ed Cook

(company name) Thunderbird Drilling, Inc. (phone) 316-685-1441

were: Order 160 sh. 50 pro mix - 4% Gel - 3% Gel. U. + 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3350' w/ 20 sh. 2nd plug C 540' w/ 80 sh. 3rd plug C 350' w/ 40 sh. 4th plug - solid bridge of bulls + plug C 40' w/ 10 sh.

Signed [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:00 PM Day: 23 Month: 2 Year: 19 83

ACTUAL PLUGGING REPORT 8 5/8" - 330' S.P. cur. w/ 250 sh. 2% Gel - 3% Gel. U.

Ordered 160 sh. 50 pro mix - 4% Gel - 3% Gel. U. + 8 5/8" plug - spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3350' w/ 20 sh. 2nd plug C 540' w/ 80 sh. 3rd plug C 350' w/ 40 sh. 4th plug - solid - bridge of bulls + plug C 40' w/ 10 sh. Circulated 10 sh in rat hole.

Remarks: Drilled in to Oriskany

RECEIVED STATE CORPORATION COMMISSION

MAR 14 1983 03-14-1983 CONSERVATION DIVISION Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED

DATE 3-30-83

INV. NO. 3797-W