

6 041123

correct spot

E-24, 483

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 167-06,196 -0003  
NE SW SW SEC. 32, T 11 S, R 15 W XXX

TECHNICIAN'S PLUGGING REPORT

Operator License # 6854

Operator: B. P. Exploration Inc.  
Name & Address: Box 37  
Gorham, Ks. 67640

990 feet from S section line

4290 feet from E section line

Lease Name Dodge Well # 2

County Russell 103.38

Well Total Depth 3181 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 1/4 feet 2359' w/100 sks

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hoys, Ks.

Company to plug at: Hour: 9:00AM Day: 26 Month: Dec Year: 19 89

Plugging proposal received from Joel Stull

(company name) B. P. Exp (phone)

were: 5 3/16" at 2869' w/80 sks cement: (1985) 4 1/2" liner at 2570' to surface w/130 sks:

casing sq at 512-528' w/200 sks: Annular space cement from at 528' to surf. See attached wellbore sketch: Perf at 2606' - 3064'. Ordered 420 sks

65/35 poz. 8% gel 2% cal cl w/5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 3:05PM Day: 26 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Set EZSV at 2500': sq 140 sks cement w/500# psi to

plug bottom: circ cement from 2500' to 2100': pulled tbg and perf at 2200': set EZSV at 2100' and sq 75 sks cement out. Perf at 2200' w/450# psi: stung out and circ

120 sks cement to circ at surf: Perf casing at 1000': Ptmped in casing w/

85 sks cement and 450# psi.

RECEIVED STATE CORPORATION COMMISSION

JAN 17 1990

01-17-90 CONSERVATION DIVISION Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

\* spot location on computer map.

INVOICED JAN 24 1990

Gib. S

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel

INV. NO. 27088