

5-1115-167-36597-0002

6 040905

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 5-8-45  
NE NE  
SW SE NW, SEC. 32, T 11 S, R 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613

Operator: Quinoco  
Name & Address: 4582 S. Ulster St. Parkwy  
S: 1700 Box 378111  
Denver, Colorado 80237

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

Lease Name Booth F.A. Well # A-1

County Russell 96.75

Well Total Depth 2977 feet

Conductor Pipe: Size 20 feet 35' cmt NA

Surface Casing: Size 10 3/4 feet 2400' cmt NA

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Cementing License Number \_\_\_\_\_

Address Hays, Ks. 67601

Company to plug at: Hour: 5:00PM Day: 9-10 Month: June Year: 19 88

Plugging proposal received from Lauren Herl

(company name) Quinoco (phone) \_\_\_\_\_

were: 6 5/8" casing set at 2910' w/25 sks cement.

Perfs at 2910' wo 2923'. Sq at 503' to surface w/450 sks. Pkr and tubing hung up at 2870'.

~~Ordered 200 sks Common Cement plus ordered 400 sks 65/35 Poz 10% Gel w/1/4# F.C. plus 0 sks Hulls.~~

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
OCT 21 1988  
RCW  
10-21-88

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations abandoned by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed Hour: \_\_\_\_\_ Day: 11 Month: May Year: 1988

ACTUAL PLUGGING REPORT Pumped 50 sks Common w/1/4# F.C. down tubing to plug bottom,

Displaced cement to 2800', Max psi 350#. Wait 24 hrs. Shot tubing at 2700' could not

pull. Shot tubing at 2000', couldn't pull. Shot tubing at 1520', couldnot pull.

Pumped 130 sks 60/40 Poz 6% Gel w/1/4# F.C. disp cement to 800', (max psi 450#) Shot at

800' pulled tubing. Hooked up 6 5/8" casing, pumped in add. 200 sks 65/35 Poz 10% Gel w/1/4

F.C. Max psi 450# SI 200#. Pressured up 10 3/4" casing to 700#.

Remarks: Max psi 450# Shut in 200#. (If additional description is necessary, use BACK of this form.)

INVOICED  
Please ~~do not~~ observe this plugging.

DATE 10-26-88

Signed Dennis L. Hamel (TECHNICIAN)  
Dennis Hamel

INV. NO. 22721