

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19025-00-01
Spot: SWSESW Sec/Twnshp/Rge: 32-11S-15W
330 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: FRANK BOOTH Well Number: 1
County: RUSSELL Total Vertical Depth: 3140 feet

Operator License No.: 31142 Conductor Pipe: Size 10.75 feet: 30
Op Name: PETROLEUM PROPERTY SERVICES, INC Surface Casing: Size 7 feet: 2806 100 SX CMT \$102.05
Address: 155 N. MARKET, STE 1010 Production: Size 5.5 feet: 3048 200 SX CMT
WICHITA, KS 67202 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/26/2001 2:00 PM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC
Proposal Rcvd. from: LEON KUHN Company: PETROLEUM PROPERTY SERVICE Phone: (316) 265-3351

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 300 sxs cement and 600# hulls.
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/26/2001 4:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

10 3/4" Conductor at 30'. 7" S.P. at 2806' w/100 sxs cement.
5 1/2" casing at 3048' w/200 sxs cement.
September 1950 perforated at 850' and squeezed with 400 sxs to surface - shut in at 500#.
Ran tubing to 1700' and pumped 75 sxs cement with 400# hulls.
Pulled tubing to 850' and circulated with 140 sxs cement and 100# hulls.
Pulled all tubing and squeezed 35 sxs cement to Max. P.S.I. 1000#. Held solid. No S.I.P.
7" x 5 1/2" annulus full of cement - took nothing.
Total of 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Dakota 112' - 362'.
Anhydrite 790' - 810'.
Salt Section 1145' - 1375'.

INVOICED
03-07-2001
2001061426
RECEIVED
STATE CORPORATION COMMISSION
FEB - 5 2001
CONSERVATION DIVISION
RWO
02-05-01

Remarks: ALLIED CEMENTING COMPANY. CHEYENNE TANK - WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

SNOWDEN & McSWEENEY

#1 FRANK BOOTH

32-11-15W
SW SE SW

Contr. _____

RUSSELL County

E. 1743

Comm. 11-12-25

Comp. 1-24-25

IP _____

105 BOPD

Tops	Depth	Datum
LANS	2837	
TD	3056	

Casing

5" 3051

OWDD: 3-19-40

OTD 2889

OLD POT 9½ BOPD

DDTD-3146

POTD 3453

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS