

4-010467

15-167-06195-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1960

NW NW SE /4 SEC. 32, 11 S, 15 W
2310 feet from S section line
2310 feet from E section line

Operator license# 5363

Lease: Kollman Well# 2

Operator: Berexco, Inc.

County: Russell

106.76

Address: P.O. Box 723
Hays, Kansas 67601

7/17

Well total depth 3285 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 150 feet

Aband. oil well Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: _____ License# _____

Address: _____

Company to plug at: Hour: 11:00 A.M. Day: 17 Month: July Year: 2000

Plugging proposal received from: Dennis Kirmer

Company: Berexco, Inc. Phone: KANSAS CORPORATION COMMISSION

RECEIVED

Were: _____

JUL 24 2000
07-24-00

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Case Morris

Plugging operations attended by agent? All [], Part [], None []

Completed: Hour: 1:30 P.M., Day: 17, Month: July, Year: 2000

Actual plugging report: Perforated at 1475' - 860' - 425'. Ran tubing to 2015'. Pumped 100
sxs 60/40 pozmix - 10% gel cement with 200# hulls. Cement circulated. Pulled tubing.
Pressured backside to P.S.I. 400#. Tied onto casing and pumped 100 sxs cement with 200#
hulls. Max. P.S.I. 1000#. S.I.P.0#.

Remarks: _____

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES NO _____

Plugged through TUBING , CASING _____ Elevation: _____ GL

I did [] / did not [] observe the plugging. Case Morris
(agent)

INVOICED
DATE 7/25/00
WV. NO. 1060130

Form CP-2/3