

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01764-00-00
Spot: CSESESW Sec/Twnshp/Rge: 32-11S-15W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: BOOTH Well Number: 6
County: RUSSELL Total Vertical Depth: 3166 feet

Operator License No.: 31142 Conductor Pipe: Size feet:
Op Name: PETROLEUM PROPERTY SERVICES, INC Surface Casing: Size 8.625 feet: 215 150 SX CMT \$102.90
Address: 155 N. MARKET, STE 1010 Production: Size 5.5 feet: 3152 125 SX CMT
WICHITA, KS 67202 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/26/2001 8:00 AM

Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC

Proposal Rcvd. from: LEON KUHN Company: PETROLEUM PROPERTY SERVICE Phone: (316) 265-3351

Proposed According to KCC Rules & Regulations.
Plugging Ordered 300 sxs cement and 600# hulls.
Method: Plug thru tubing. Tubing fish at 2795'.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/26/2001 10:30 AM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 215' w/150 sxs. 5 1/2" casing at 3152' w/125 sxs.
Squeezed on April 1959 at 358' w/150 sxs cement.
Tied to 8 5/8" - pressured to 500# - took no cement.
Ran tubing to 2000' - pumped 75 sxs cement with 400# hulls.
Pulled tubing to 1000' - circulated with 100 sxs cement and 100# hulls.
Pulled all tubing and squeezed 5 1/2" casing with 100 sxs cement and 500# hulls to Max. P.S.I. 500#. S.I.P. 100#.
Total of 275 sxs 60/40 pozmix - 10% gel and 500# hulls.
Dakota at 112' - 362'.
Anhydrite 790' - 810'.
Salt Section 1145' - 1375'.

INVOICED
DATE 03-07-2001
NO. 2001061426

RECEIVED
STATE CORPORATION COMMISSION
RCVD KCC
FEB - 5 2001
02-05-01
COMM. ENGINEER

Remarks: ALLIED CEMENTING COMPANY. CHEYENNE TANK - WATER.

Plugged through: TBG

District: 04

MO

Signed

Roger L. Moses

(TECHNICIAN)

AYLWARD DRILLING

#6 BOOTH

32-11-15W 33
SE SE SW

Contr. AYLWARD DRLG

RUSSELL County

E 1742 RB Comm.

Comp. 2-8-57

IP 25 BOPD

Tops	Depth	Datum
DOD	2809	-1067
-KC	2840	-1098
REAG	3151	-1109
TD	3162	-1120

Casing

8" 215

5" 3152

DST 2805-75, 50' SL OCM & WTR
 DD 3162; PB 3080; PERF 2836-39
 PERF 2842-46; ACID 500; WTR; PB
 2826; PERF 2805-11; ACID 500

GORHAM POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS