

6-3

67

To: 6 031265
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 167-22,854-0000
C N/2 S/2 NW SEC. 34, T. 11 S, R. 15 W/E XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Operator: Frontier Oil Co.
Name & Address 125 N. Market Suite 1720
Wichita, Ks. 67202

3630 feet from S section line

3960 feet from E section line

Lease Name Abbott Well # 4

County Russell 107.06

Well Total Depth 3294 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger License Number _____
Address Wichita, Ks.

Company to plug at: Hour: AM Day: 3rd Month: June Year: 19 89

Plugging proposal received from Bill Ayers

(company name) Red Tiger (phone) _____

were: 8 5/8" set at 209' w/130 sks cwc. Circ hole w/no less than 36 vis mud

w/no loss or gain of fluid. Balance plugs w/mud. Order 205 sks 60/40 poz 6% gel 3% cal cl

Allied Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:15AM Day: 3 Month: June Year: 19 89

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe w/25 sks at 3294'

25 sks at 900'

90 sks at 650' w/hulls

40 sks at 250'

10 sks at 40' wiper plug w/d

Circ 15 sks igather

Remarks: No arb. Anhy 875' - 913' Elev. 1796'
(If additional description is necessary, use BACK of this form.)

JUN 21 1989

I (did/did not) observe this plugging.

INVOICED
DATE 6-23-89

INV. NO. 25107

Lib S.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

CONSERVATION DIVISION
Wichita, Kansas