

To: 6 062436
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-13
API NUMBER 15- 1670038700-00 231 R

SE, SEC. 35, T 11 S, R 15 W/EX

2310 feet from S section line

2310 feet from E section line

Lease Name Eulert Well # A1 (5)

County Russell 107.96

Well Total Depth 3322 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 215'

TECHNICIAN'S PLUGGING REPORT

Operator License # 30385

Operator: Liedtke Partners

Name &

Address P.O. Box 1605

Great Bend, Kansas 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, Kansas 67530

Company to plug at: Hour: 9:00 A.M. Day: 13 Month: June Year: 19 91

Plugging proposal received from Charles Steinkamp, Box 342, Great Bend, Kansas 67530

(company name) Liedtke Partners 316-793-9711 (phone) 316-793-8061

were: Order 50 sks. common - 350 sks. 60/40 poznix - 10% Gel. - 5 sks. hulls.

Elev. 1863' Anhy. 920' Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 P.M. Day: 13 Month: June Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" set at 215' w/115 sks. 4 1/2" set at 3316' w/225 sks.

Top perf. at 3049'. Ran tubing to 3014' spotted 50sks. common. Pulled tubing to 900' and spotted 335 sks. of 60/40 poznix. 10% Gel. w/75 P.S.I. Pulled all tubing.

Hooked on to 8 5/8" - 15 sks. cement to surface. 60/40 poznix - 10% Gel.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1991

Remarks: By Allied. Shot hole at 440' and 930'.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

~~INVOICED~~ Observe this plugging.

Signed Gilbert G. Scheck
(TECHNICIAN) E.A.S.

DATE JUL 19 1991

INV. NO. 32316