

4-25

33  
R

6-060256

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-167-22,972-00-00  
50' E. of  
SW NE /4 SEC. 35, 11 S, 15 W  
3300 feet from S section line  
1950 feet from E section line

Operator license# 6194 Lease Eulert East well # 1

Operator: E.S.P. Development, Inc. County Russell

Address: R.R. 1 Well total depth 3390 feet 110.17  
Box 18 Conductor Pipe: 0 inch @ 0 feet  
Paradise, Kansas 67658 Surface pipe 8 5/8 Inch @ 206 feet

Aband. oil well    , Gas well    , Input well    , SWD    , D & A X

Plugging contractor: Western Kansas Drilling License#    

Address: Hays, Kansas 67601

Company to plug at: Hour:     Day: 25 Month: April Year: 91

Plugging proposal received from: Frank Taggart

Company: Western Kansas Drilling Phone:    

Were: Order 175 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.  
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 10 1991

Plugging Proposal Received by: Herb Deines CONSERVATION DIVISION  
Plugging operations attended by agent? All [     ], Part [     ], No WICHITA, KS

Completed: Hour: 8:00A.M., Day: 25, Month: April, Year: 91

Actual plugging report:  
1st. plug at 3348' with 25 sxs. - Arbuckle 3348'.  
2nd. plug at 960' with 25 sxs. - Anhydrite 937' - 968'.  
3rd. plug at 540' with 60 sxs. - Dakota 238' - 538'.  
4th. plug at 225' with 40 sxs. - Surface pipe to 206'.  
5th. plug at 40' with 10 sxs.  
15 sxs. in Rathole.

Remarks: Allied Cementing.

I  did  did not [ X ] observe the plugging.

Herb Deines

INVOICED  
DATE 10-15-91  
33352

Herb S.

(agent)  
Form CP-2/3