

4-050148

10-27 39
167-05134-00-01
E-14,451
R

TO:

API number: 15-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

~~AWMSE~~
NE NW SE /4 SEC. 35, 11 S, 15 W
2310 2210 feet from S section line
1650 feet from E section line

Operator license# 30385

Lease ^{RTKCC} Eulert A Unit well# 6

Operator: Liedtke Operating Corporation County Russell

Address: 370 17th. St. Suite 3600
Denver, Colorado 80202
(303) 595-8405

Well total depth 3344 feet ^{108.68}
Conductor Pipe: _____ inch @ _____ feet
Surface Pipe: 8 5/8 inch @ 926 feet

Aband. oil well _____, Gas well _____, Input well X, SWD _____, D & A _____

Plugging contractor: Chase Well Service License# 6123

Address: P.O. Box 355 Great Bend, Kansas 67530 (316) 793-7456

Company to plug at: Hour: PM Day: 27 Month: October Year: 1992

Plugging proposal received from: Richard Tennant

Company: Liedtke Operating Corporation phone: (316) 793-7456

Were: 8-5/8 surface csg. set @ 926 ft with 375 sks.

5-1/2 production csg set @ 3334 ft with 375 sks.

Perfs Topeka 2749-53, Plattsmouth 2930-34, and LKC 3020-3239

Elevation 1866 ft. Anhydrite 920 ft. Docket No. E-14,451

Ordered 70 sacks commom cement, 370 sacks 60/40 poz 8% gel, and 100 lbs. hulls.

Plugging Proposal Received by: Richard Tennant

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:00 PM, Day: 27, Month: October, Year: 1992

Actual plugging report: Ran tbq. to bottom. Pumped 70 sks. commom cement down tbq. Pulled tbq. to 2940'. Pumped 100 sks 60/40 poz 8% gel down tbq. Pulled tbq. to 1290'. Pumped 100 sks. 60/40 poz 8% gel, cement circulated to surface. Pulled rest of tbq. tied onto 5-1/2 csg. squeezed 145 sks. 60/40 poz 8% gel and 100 lbs. hulls down csg. at 400 max. psi. and 100 shut-in psi. Squeezed 25 sks. 60/40 poz 8% gel down backside at 500 max. psi. and 350 shut-in psi.

Allied Cementing Company

STATE CORPORATION COMMISSION

Remarks:

NOV 9 1992

I did [X] did not [] observe the plugging.

Marvin L. Miller
Marvin L. Miller

DATE 11-23-92

#0

Form CP-2/3

WV. NO. 36854