

6-8

4-020051

E-14,451

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-167 05133-00-01
C S2 NE SE /4 SEC. 35, 11 S, 15 W
1650 feet from S section line
660 feet from E section line

Operator license# 4058
Operator: American Warrior, Inc.
Address: P.O. Box 399
Garden City, Kansas 67846

JUN 19 1998
06-18-98

Lease: Eulert Well # 8
County: Russell 108.07
Well total depth 3325 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 907 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: American Warrior, Inc. License# 4058

Address: P.O. Box 399 - Garden City, Kansas 67846

Company to plug at: Hour: 1:30 P.M. Day: 8 Month: June Year: 1998

Plugging proposal received from: Kevin Wiles

Company: American Warrior, Inc. Phone: 316-275-2963

Were: FL at 900'. 5 1/2" at 3314' w/150 sxs. Cast Iron BP at 3290'.
Perfs at 3006' - 3221'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:00 P.M., Day: 8, Month: June, Year: 1998

Actual plugging report: Allied cemented with 75 sxs 60/40 pozmix - 10% gel with 200# hulls, followed with 17 sxs gel spacer with 200# hulls. Mixed 65 sxs. Hooked on 8 5/8" and pumped 105 sxs cement with 200# hulls. Max. P.S.I. 400#. S.I.P. 200#. Topped off 5 1/2" with 20 sxs. Max. P.S.I. 600#. S.I.P. 500#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC X, NO
Plugged through TUBING, CASING X

Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation: 1845 GL

I did [X] / did not [] observe the plugging.

INVOICED

Jay Pfeifer (agent)

Form CP-2/3

DATE JUN 19 1998

WV# 50787

HO