

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

Drilled February 1926

API NUMBER 15-167-06196-0003 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR BP Exploration Inc. OPERATORS LICENSE NO. 06854 ^{6/60}

ADDRESS P.O. Box 4587 Houston, Tx. 77210 PHONE # (713) 552-8500

LEASE (FARM) Dodge WELL NO. 2 WELL LOCATION NE SW SW COUNTY Russell

SEC. 32 TWP. 11S RGE. 15 ~~(S)~~(W) TOTAL DEPTH 3181' PLUG BACK TD 3075'

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL XXX DOCKET NO. E-24,483

see attached SURFACE CASING SIZE 8 1/4" SET AT 2359' CEMENTED WITH 100 sx top jobs SACKS
wellbore sketch CASING SIZE 6 5/8" SET AT 2839' CEMENTED WITH none SACKS

PERFORATED AT see wellbore schematic

CONDITION OF WELL: GOOD XXXX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1) set retainer at 2500', squeeze all perforations with 150 sx 65-35 Pozmix; 2) spot cement on top of retainer to 1200', 65 sx Pozmix; 3) spot second cement plug from 1200' to surface using 60 sx of Pozmix; 4) cut
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes _____ IS ACO-1 FILED? YES
^{RECEIVED}
^{NOV 13 1989}
^{CONSERVATION DIVISION}
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Nov. 27, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Joel Stull - field supervisor PHONE # (913) 637-5290

ADDRESS Gorham Kansas 67640

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 5287

ADDRESS 1100 East 8th St. Hays Kansas 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Joanna Dnesko
(Operator or Agent)

DATE: 11-10-89

4

Casing: 5 3/16" set at 2869' cemented with 80 sx
4 1/2" liner 0-2570' cemented with 130 sx (TOC: surface)
4 1/2" liner 2815-3109' cemented with 350 sx
3 1/2" liner 3100-3179' no cement
PBSD: 3075' with bridge plug and cement

Plugging method:

4) casings below plow depth, weld on steel plate.

Note: When well was converted to an injection well, the 4 1/2" liner was run from surface to 2570' and cemented to surface. The 100 sx top job was performed on the 8 1/4" casing. There is no need to perforate the 4-1/2" casing below the anhydrite interval because it is already covered with cement.



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH MCCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

THIS NOTICE
FEB 13 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

November 13, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

BP Exploration, Inc.
P.O. Box 4587
Houston, TX 77210

Dodge 2
NE SW SW
32-11-15W
Russell County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200