

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-167-01763-0001

API NUMBER 3/8/56
 LEASE NAME Booth
 WELL NUMBER 5W
1090 Ft. from S Section Line
3630 Ft. from E Section Line
 SEC. 32 TWP. 11 RGE. 15 (E) or (W)
 COUNTY Russell
 Date Well Completed 3/8/56
 Plugging Commenced 10/19/88
 Plugging Completed 10/19/88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR GEAR PETROLEUM CO., INC.
 ADDRESS 1075 KSB Bldg. 125 N. Market Wichita, KS 67202
 PHONE# (316) 265-3351 OPERATORS LICENSE NO. 5151
 Character of Well Input
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes
 Which KCC Office did you notify? District #4 Gilbert Scheck
 Is ACO-1 filed? NO If not, is well log attached? filed with application to plug
 Producing Formation LKC Arbuckle Depth to Top 2843 Bottom 3078
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
LKC	OIL	3067	70	8 5/8	106	NONE
Arubckle	OIL	3156	58	5 1/2	3160	NONE

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 22 1988
 CONSERVATION DIVISION
 Wichita, Kansas
 RWO
 11-22-88

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump down 5 1/2 casing 50 SX common followed by 150 SX 60/40 poz 6% gel, 10 SX gel mixed with 5 SX hulls in 150 SX 60/40 poz, 6% gel. Cement to surface with final pressure of 500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GEAR PETROLEUM CO., INC. License No. 5151
 Address 1075 KSB Bldg. 125 N. Market Wichita, KS 67202
 STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jim Thatcher (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

PAULETTA K. ENGELS
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appl. Exp. 8/1/89

(Signature) Jim Thatcher
 (Address) 1075 KSB Bldg. 125 N. Market
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 21 day of October, 1988

Pauletta K. Engels
 Notary Public

My Commission Expires: 8/1/89

15-167-01763-0004

GEAR PETROLEUM CO., INC.

October 20, 1988


State Corporation Commission
Conservation Division
200 Colorado Derby Bldg.
Wichita, KS 67202

RE: Booth 5W
NW SE SW Sec. 32-11S-15W
Russell County, Kansas
Docket #E11553

Gentlemen:

The subject "LKC" injection well has been shut in since it was acquired from Aylward Drilling in 1984. We were cleaning out the well and found it to be un-useable as it was full of scale and sand. Since a pulling unit was rigged up over the well we called District #4 and the well was plugged under their supervision 10/19/88. The plugging report will be filed as soon as we have the cementing tickets.

Sincerely yours,



Jim Thatcher

JT/pe

encl.

cc: Max Parsons

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1988

CONSERVATION DIVISION
Wichita, Kansas