

WELL PLUGGING RECORD

State Of Kansas
State Corporation Commission
130 S. Market, Room 2078
Wichita, KS 67202

Lease Operator: Petroleum Property Services, Inc.
155 N. Market #1000, Wichita, KS 67202

Phone 316-265-3351

Character of Well:

API Number: 15-167-01764-00-00

Lease Name: BOOTH

Well Number: 6

330 Ft. From S Section Line

2970 Ft. From E Section Line

Sec: 32 TWP: 11S RGE: 15W

Operators License No. 31142 RUSSELL County:

Date Well Completed: 1/1957

Plugging Commenced: 1/26/2001

Plugging Completed: 1/26/2001

The plugging proposal was approved on: 1/23/2001

by: HERB DEINES

KCC District Agent

Is ACO-1 Filed: NO

If not, is well log attached? YES

Producing Formation:

Depth to Top

Bottom

T.D.

LKC

2805

2846

3166

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

<u>Formation</u>	<u>Content</u>	<u>From</u>	<u>To</u>
LKC	O&W	2805	2846

<u>Size</u>	<u>Put In</u>	<u>Pulled Out</u>
8 5/8	215	0
5 1/2	3152	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or plugs were used, state the character of same and depth place, from ___feet to ___feet each set.

4/59 SQZ CSG LEAK @ 358 WITH 150 SX. 1/2001 CONNECT PUMP TRUCK TO 8 5/8-5 1/2 ANNULUS, COULD NOT PUMP IN @ 500#. RUN TUBING TO 2000, PUMP 75 SX 60/40 POZ 10% GEL AND 400# HULLS. PULL TUBING TO 1000 AND PUMP 100 SX 60/40 POZ 10% GEL, 100# HULLS TO SURFACE. PULL TUBING AND PUMP DOWN 5 1/2, 100 SX 60/40 POZ, 10% GEL, 500# HULLS. MAX PRESSURE 500#, SHUT IN PRESSURE 100#. HOLE STAYED FULL

Plugging Contractor: PETROLEUM PROPERTY SERVICES

License No. 31142

Address: 155 NORTH MARKET #1010, WICHITA, KS 67202

Name of Party Responsible For Plugging Fees: Petroleum Property Services, Inc.

STATE OF: KANSAS

COUNTY OF: SEDGWICK, SS.

R.J. Thatcher

(Employee of Operator) or (Operator), of above-

described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature: R.J. Thatcher

Address: 3535 American Drive, Colorado Springs, CO 80917

SUBSCRIBED AND SWORN TO before me this 15th day of March, 2001

RECEIVED
STATE CORPORATION COMMISSION

Rosann M. Schippers

Notary Public

My Commission Expires: 9/08/03

ROSANN M. SCHIPPERS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 9/08/03

MAR 16 2001
03-16-01
CONSERVATION DIVISION
State of Kansas

OR

15-167-01764-0000

BOOTH #6

Casing Record:

8 5/8" - 215'
5 1/2" - 3152'

Company: Aylward Drilling Company
Contractor: Aylward Drilling Company

Commenced: December 11, 1956
Completed: December 21, 1956

Location: SE SE SW 32-11-15W
Russell County
Kansas

Elevation: 1742 KB

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand, Shale and Shells	0	110	Set 8 5/8" pipe @ 215' w/150 sx cement
Shale and Shells	110	215	
Shale and Sand	215	510	Geological Tops:
Shale, Shells & Redbed	510	790	
Anhydrite	790	815	Anhydrite 790
Shale and Shells	815	1390	Topeka 2566
Shale and Lime	1390	1430	Heebner 2788
Shale and Shells	1430	1550	Toronto 2809
Lime	1550	1660	Lansing 2840
Broken Lime	1660	1745	Base Kan. City 3072
Shale and Shells	1745	1810	Reagan 3151
Shale and Lime	1810	1845	RTD 3156
Lime and Shale	1845	1945	
Shale and Lime	1945	2115	
Lime and Shale	2115	2170	DST 2740-65' Open 1 hr.; good blow
Shale, Brk.	2170	2185	throughout. Rec. 1620' Water
Shale and Lime	2185	2245	BHP 1175/20 min.; FP 60.7 - 725'
Shale	2245	2390	
Shale and Shells	2390	2665	DST 2794-2825' Open 1 hr.; good blow
Shale and Lime	2665	2825	throughout. Rec. 200' free gas in drill
Lime	2825	3140	pipe plus 100' O&GCM; BHP 40.7/20 min.
Diamond Core	3140	3156 T.D.	
			DST 2821-75' Open 1 hr. Fair blow
			throughout. Rec. 27' Sl. OCM, 90' very
			slightly OC watery mud.
			BHP 175.7/20 min.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesser

Subscribed and sworn to before me this 28th day of December, 1956.

Duane Jessup
Notary Public

My commission expires December 11, 1957

ALLIED CEMENTING CO., INC. 5123

15-167-01764-00-00

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: K

DATE <u>1-26-00</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START	JOB FINISH <u>10:30 am</u>
LEASE <u>Booth</u>	WELL # <u>6</u>	LOCATION <u>Fairport Z. 2nd</u>			COUNTY <u>Russell</u>	STATE <u>Ks</u>	

OLD OR NEW (Circle one)

CONTRACTOR Plain Well Service

TYPE OF JOB Re

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2 1/2 DEPTH 200

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

EQUIPMENT

PUMP TRUCK # <u>177</u>	CEMENTER <u>W. Galt</u>
	HELPER <u>Law</u>
BULK TRUCK # <u>291</u>	DRIVER <u>Karin</u>
BULK TRUCK # _____	DRIVER _____

REMARKS:

75 sk @ 2000 w/400' hells
100 sk @ 1000' w/100' hells use cement
Pulled tubing that onto 5 1/2 mixed
100 sk
Max psi 500' shot 100' #1
Pressure 8 1/2 to 500'

CHARGE TO: POST

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co. Inc.

OWNER

CEMENT AMOUNT ORDERED 275 6/40 10% gel
500' hells

COMMON	<u>25</u>	@	<u>6.35</u>	<u>1047.25</u>
POZMIX	<u>110</u>	@	<u>3.25</u>	<u>357.50</u>
GEL	<u>19</u>	@	<u>4.50</u>	<u>85.50</u>
CHLORIDE		@		
<u>Hells</u>	<u>5</u>	@	<u>18.00</u>	<u>90.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>280</u>	@	<u>1.05</u>	<u>294.00</u>
MILEAGE	<u>44 1/2</u>	@	<u>5.00</u>	<u>224.00</u>
TOTAL				<u>2193.25</u>

SERVICE

DEPTH OF JOB				
PUMP TRUCK CHARGE				<u>450.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>20</u>	@	<u>3.00</u>	<u>60.00</u>
PLUG		@		
		@		
		@		
TOTAL				<u>510.00</u>

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		