

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 206 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-167-06196-0003

LEASE NAME Dodge

WELL NUMBER 2

990 Ft. from S Section Line

4,290 Ft. from E Section Line

SEC. 32 TWP. 11 RGE. 15 (R) or (W)

COUNTY RUSSELL

Date Well Completed 10/03/45

Plugging Commenced 12/20/89

Plugging Completed 12/26/89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR BP Exploration

ADDRESS 9401 SW Fwy, Houston, TX 77074

PHONE# (713) 272-5000 OPERATORS LICENSE NO. 06854

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/18/89 (date)

by Dennis Hammett (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation top-L-KC Depth to Top 2,600 Bottom 3174 T.D. 3181

PBTD 3075

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topeka	(2600-2869) oil	0	2359	8 1/2	2359	6'
Lansing	(2869-3174) oil	0	2839	6-5/8	2839	6'
Reagan Sand	(3174-NDE) oil	0	2869	5-3/16	2869	6'
		0	2570	4 1/2	2570	6'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set EZSV at 2,500'. Pumped 130 sx cement below retainer. Shot 2 holes at 2,200. Spotted cement to 2,100. Set EZSV @ 2,100. Pumped 75 sx cement below. Shot 2 holes at 1,000'. Circulated 120 sx cement to surface. Tied onto 4 1/2" csg and pumped 85 sx down it. Cement was 65/35 POZ 2/8% gel and 2% CaCl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address 1100 E. 8th, Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BP Exploration

STATE OF Texas COUNTY OF Harris, ss.


Scott Marshall (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott Marshall

(Address) 9401 SW Fwy, Houston, TX 77074

SWORN TO before me this 15th day of January, 19 90

Hilda I. Goodman
 Notary Public



My Commission Expires: 1-18-92

5287
 RECEIVED
 STATE CORPORATION COMMISSION
 JAN 17 1990
 CONSERVATION DIVISION
 Wichita, Kansas

1989

DODGE #2 SKID FAIRPORT FIELD

15-167-06196-0003

CEMENT →

REPAIRED CASING LEAK (1979) W/ 200 SX CMT DEPTH 512-528'

1000'
50 SHEETS
22-141
100 SHEETS
22-142
200 SHEETS
22-144
AMPAD

2000'

1985 RAN 4 1/2" WELDED LINER TO 2570' CMT 130SX

8 1/4" @ 2359' 100SX TOP JOB (1986)

PERFS

6 5/8" @ 2839', NO CMT.

3000'

DEEPEMED TO 3181' IN 1945; RAN 4 1/2" & 3 1/2" LINERS

5 3/16" @ 2869', 80 SX CMT

4 1/2" 2815' - 3109', 350 SX

3 1/2" 3100 - 3179', loose

SET BP @ 3075' W/ 1SX CMT

RECEIVED STATE CORPORATION COMMISSION

NOV 15 1985

CONSERVATION DIVISION
Wichita, Kansas

4000'

PERFORATIONS

- TOPEKA: 2606-08'
- TORONTO: 2840-43', 2843-47'
- L-KC: 2874-76', 2878-84', 2892-94', 2906-08', 2917-19', 2928-36', 2969-73', 2958-66', 3011-14', 3039-41', 3052-56', 3061-64'
- PLATTSMOUTH: 2794-98', 2806-11'

BLOCK SQUEEZE

1937 : 2830-40', USED 50SX CEMENT