

LEASE NAME Kollman 2

WELL NUMBER 2

 Ft. from S Section Line

NW NW SE Ft. from E Section Line

SEC. 32 TWP. 11 RGE. 15W (E) or (W)

COUNTY Russell

Date Well Completed 2-24-60

Plugging Commenced 7-17-2000

Plugging Completed 7-17-2000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/17/2000 (date)

BY Case Morris (KCC District Agent's Name)

Is ACO-1 filed? if not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3285

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	150	8 5/8		
	Production	0	3285	4 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Ran openended to 2015'. Mix 100 sk. 60/40 pos, 10% gel, 300 hulls. Cement circulate to surface. Pull tubing. Tie to 8 5/8 press. up to 8 5/8 held. Tie on to 4 1/2 csg. Mix 100 sk. with 200# hulls. Pressure to 800#. Shut in at 400#. Held.


Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Dennis Kirmer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.



(Signature) Dennis Kirmer

(Address) Box 723 Hays, KS 67601

RECEIVED SUBSCRIBED AND SWORN TO before me this 27 day of July 19 2000
 STATE CORPORATION COMMISSION

Rosemary Smith
 Notary Public

Commission Expires: 5-10-03

