


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

NORTH



Locate well correctly on above  
Section Flat

RUSSELL County. Sec. 32 Twp. 11 Rge. (E) 15 (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SE/4  
Lease Owner. B & R DRILLING CO.  
Lease Name. KOLLMAN Well No. 1  
Office Address. RUSSELL, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed. 7/5 19.47  
Application for plugging filed. 7/1 19.47  
Application for plugging approved. 7/1 19.47  
Plugging commenced. 7/1 19.47  
Plugging completed. 7/5 19.47  
Reason for abandonment of well or producing formation. DRY HOLE

If a producing well is abandoned, date of last production. 19.  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? YES

Name of Conservation Agent who supervised plugging of this well. H. W. KERR  
Producing formation. Depth to top. Bottom. Total Depth of Well. 3165 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	552'	NONE
				5 1/2"	3147'	2197'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

FILLED HOLE W/SAND FROM 2900' TO 2820' - FILLED HOLE W/SAND FROM 2820' TO 2570' -  
DUMPED 5 SX CEMENT @ 2570' - SHOT PIPE @ 2400'-2300'-2200' - PULLED 70 JTS PIPE -  
FILLED HOLE W/MUD TO 250' - DUMPED 15 SX CEMENT - FILLED W/MUD TO 30' - DUMPED 10  
SACKS CEMENT.

JUL 16 1947  
REC'D 07-16-47

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to. B & R DRILLING CO.  
Address. RUSSELL, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
C. L. ROBERTS (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature) *C. L. Roberts*  
RUSSELL, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 15TH day of JULY, 1947.  
*Clara Sumner*  
Notary Public.

My commission expires 6/17/50



B & R DRILLING, INC.  
KOLLIAN #1

SEC. 32 TWP. 11 RGE. 15  
COUNTY: RUSSELL, KANSAS

TOTAL DEPTH: 3155'  
COST: 5/18/47 COMP: 6/5/47

TOP TOPERA = 2525  
TOP LAINING N.C. = 2834

CASING  
20 JOBS. 8 5/8" SET AT 552'  
102 JOBS. 5 1/2" SET AT 3147'

CEMENT  
275 SK  
150 SK

FORMATION:

DEPTH:

SURFACE CLAY & POST ROCK	30'
WATER, SAND & GRAVEL	65
SHALE & SHELLS	140
SAND	165
SHALE, SHELLS & IRON	235
SHALE & SHELLS OF PYRITE	282
SAND, SHALE, & SHELLS	420
RED SHALE, SAND, SHALE & SHELLS	552
RED BED & SHALE	765
ANHYDRITE	810
SHALE & SHELLS	1195
SALT & SHALE	1405
SHALE & SHELLS	1450
LIME & SHALE	1490
LIME	1545
SHALE & LIME	1725
LIME	1845
LIME & SHALE	2020
LIME & BROKEN LIME	2110
BROKEN LIME	2140
LIME & SHALE	2585
LIME	3125
LIME & SAND	3157
DERRICK FLOOR CORRECTION	3155
LIME	3165

STATE OF KANSAS )  
                          ) SS  
RUSSELL COUNTY )

I HEREBY CERTIFY THAT THE ABOVE INFORMATION IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6TH DAY OF JUNE, 1947.

MY COMM. EXPIRES 6/17/50

*Larry L. Truitt*  
\_\_\_\_\_  
*Clara Lummel*  
\_\_\_\_\_  
NOTARY PUBLIC

JUL 16 1947

**PLUGGING**  
FILE SEC 32 T 11 R 15W  
BOOK PAGE 119 LINE 29