


15-167-01762-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Russell County. Sec. 32 Twp. 11 Rge. 15 (E) (W) X
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Okmar Oil Co.
Lease Name Abbott Well No. #1
Office Address 1130 Vickers KSB&T Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6-19-72 19
Plugging completed 6-21-72 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation Depth to top Bottom Total Depth of Well 3257' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 5 1/2" | 3238' | Plug only |
| | | | | 8 5/8" | 185' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump down 5 1/2" casing - 5 sacks gel - 3 sacks hulls - 15 sacks cement 20 sacks gel and 40 sacks cement.
Fill with 3 yards readymix.

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1972
CONSERVATION DIVISION
Wichita, Kansas
06-22-72

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of June, 1972



Sidney D. Miller
Notary Public.

My commission expires

15-167-01762-000

CONTRACTOR'S WELL LOG

OPERATOR Okmar Oil Company WELL NAME Abbott #1
LOCATION SW SW NE SEC. 32-11-15 RIG NO. 2
COUNTY Russell STATE Kansas
COMMENCEMENT DATE January 6, 1958 COMPLETION DATE January 17, 1958

LOG OF WELL

Elevation 1825' rotary bushing.
All measurements taken from the top of rotary bushing.

| FROM | TO | FORMATION | DEVIATION FROM VERTICAL | REMARKS: |
|------|------|-------------|-------------------------|----------------|
| 0 | 185 | Shale-Shell | | |
| 185 | 250 | Shale-Shell | | |
| 250 | 440 | Shale-Shell | | |
| 440 | 550 | Shale-Sand | | |
| 550 | 650 | Shale-Shell | | |
| 650 | 825 | Red Bed | | |
| 825 | 875 | Red Bed | | |
| 875 | 907 | Anhydrite | | |
| 907 | 1115 | Shale-Shell | | |
| 1115 | 1430 | Shale-Shell | | |
| 1430 | 1490 | Shale-Shell | | |
| 1490 | 1575 | Shale-Lime | | |
| 1575 | 1760 | Shale-Lime | | |
| 1760 | 1865 | Shale-Lime | | |
| 1865 | 1950 | Shale-Lime | | |
| 1950 | 2065 | Shale-Lime | | |
| 2065 | 2220 | Shale-Lime | | |
| 2220 | 2370 | Shale-Lime | | |
| 2370 | 2534 | Shale-Lime | 0° - 2500 | |
| 2534 | 2650 | Shale-Lime | | |
| 2650 | 2671 | Lime | | DST 2652-2671' |
| 2671 | 2684 | Lime | | |
| 2684 | 2768 | Lime | 0° - 2750 | |
| 2768 | 2816 | Lime | | |
| 2816 | 2860 | Lime | | DST 2830-2860' |
| 2860 | 2902 | Lime | | DST 2885-2915' |
| 2902 | 2915 | Lime | | |
| 2915 | 2945 | Lime | | DST 2930-2945' |
| 2945 | 2968 | Lime | | DST 2950-2968' |
| 2968 | 2975 | Lime | | |
| 2975 | 3030 | Lime | 0° - 3000 | |
| 3030 | 3063 | Lime | | |
| 3063 | 3110 | Lime | | |
| 3110 | 3168 | Lime | | |
| 3168 | 3177 | Lime | | DST 3115-3177' |
| 3177 | 3215 | Lime | | |
| 3215 | 3241 | Lime | | |

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1972
CONSERVATION DIVISION
Wichita, Kansas

CASING LEFT IN HOLE AFTER COMPLETION

Ran 185.43' (9 jts.) 8-5/8" OD Surface Casing.
Set 3238' (103 jts.) 5-1/2" OD Casing.

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 22nd day of January, 1958.

My commission expires: May 20, 1959

Vicky Jacobs
Vicky Jacobs, Notary Public