

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

#4 API NUMBER 15-167-36597-0002

LEASE NAME F.H. Booth

WELL NUMBER A-1

4950
~~2970~~ Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 32 TWP. 11S RGE. 15 (X) or (W)

COUNTY Russell

Date Well Completed 4-25

Plugging Commenced 6-9-88

Plugging Completed 6-10-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Quinoco Petroleum, Inc.

ADDRESS P.O. Box 378111, Denver, CO 80237

PHONE # (303) 850-7373 OPERATORS LICENSE NO. 03613

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Hays District Office - KCC Rep. Dennis Hamel

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Reagan Depth to Top 3180 Bottom 3186 T.D. 3186

Show depth and thickness of all water, oil and gas formations. *Toronto **I-KC A & B (commingled) *2605-15'
**2880-3914'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topoka	Oil	Surf	2589	8-1/4	X	No
Toronto	Oil	Surf				
I-KC "A"	Oil		2880	6-5/8	X	No
I-KC "B"	Oil	Surf				
Reagan	Oil		3180	5	X	No

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Please see reverse.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pullers License No. 6050

Address Box 347, Chase, Kansas 67524

STATE OF Colorado COUNTY OF Denver, ss.

Janet Wilkerson

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jan Wilkerson

(Address) P.O. Box 378111, Denver, CO

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 88

My Commission Expires: 9/21/88

RECEIVED
 STATE CORPORATION COMMISSION
 Notary Public
Cecilia A. Purdy
 RWP
 JUL 14 1988

07-14-88

CONSERVATION DIVISION
 Wichita, Kansas

Form CP-4
 Revised 07-86

#313.jw

Pumped 50 sx common cmt down tbg to 2800'. Shot tbg @ 2700', could not pull, shot @ 2000', could not pull, stuck @ 1520'. Pump 100 sx cmt down tbg, displace to \pm 800'. P.O. shot tbg @ 800'. RU Howco to 2-7/8" tbg, pump 3 sx hulls, 100 sx 60-40 poz mix with 1/4# flowseal/sx. RU & shot tbg @ 800', pull tbg. RU Howco to 6-5/8" csg, pump 5 sx hulls and 200 sx cmt. Hook up to 10-3/4" surf pipe. Press to 700#, held OK. Close well in.