


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Russell County. Sec. 34 Twp. 11 Rge. 15 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 990' from south, 2310' from east.
Lease Owner B. W. Shindhelm
Lease Name O. Eulert Well No. 1
Office Address Box 363, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.
Date well completed Oct. 17 1955
Application for plugging filed Oct. 27 1955
Application for plugging approved Oct. 28 1955
Plugging commenced Nov. 1 1955
Plugging completed Nov. 4 1955
Reason for abandonment of well or producing formation No production

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt
Producing formation Arbuckle Depth to top 3158' Bottom 3210' Total Depth of Well 3210 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	water	3186	3193	8 5/8	763'	None
Arbuckle	Show of oil	3160	3166	4 1/2	3210'	2512'
Kansas City	water	2848	2854			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock from 3169' to 2830'. Dumped 4 sacks cement with dump bailer. Cement plug 2830' to 2790'. Filled hole with mud from 2790' to 275'. Set rock bridge and dumped 20 sacks of cement. Top of cement 205'. Filled hole with mud to 35'. Set rock bridge. Dumped 10 sacks of cement for cap.

RCWO
11-09-55
COMMISSION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co. (Well plugging license #12)
Address Great Bend, Kansas

STATE OF _____, COUNTY OF _____, SS.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. W. Shindhelm

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 1955

My commission expires 8-23-56

Notary Public.

PLUGGING
FILE SEC 34 T 11 R 15 W
BOOK PAGE 11 LINE 38

DRILLING RECORD

15-167-00280-0000

Well No. 1 Eulert
 NW SW SE Sec 34-11S-15W
 Russell County, Kansas

Casing Record

763' of 8-5/8" OD Surface
 Pipe cemented with 500 sacks.

3210' of 4 1/2" OD Casing
 cemented with ~~300~~ sacks.

Work Commenced 9/2/55
 Drilling Commenced 9/2/55
 Drilling Completed 9/13/55
 Work Completed 9/15/55

150

WELL LOG

Surface Soil	0 to 30
Shale & Gravel	30 to 55
Sand & Shale	55 to 310
Shale & Iron	310 to 375
Sand & Clay	375 to 460
R.B. & Shale	460 to 540
Red Bed	540 to 753
Anhydrite	753 to 804
Red Bed	804 to 980
Shale & Shells	980 to 1225
Shale & Salt	1225 to 1300
Shale	1300 to 1460
Shale & Shells	1460 to 1625
Shale & Lime	1625 to 1645
Shale & Lime Stks	1645 to 1690
Lime & Shale	1690 to 2845
K.E. Lime	2848 to 2852
Lime	2852 to 2894
K.C. Lime	2894 to 2954
Lime	2954 to 2998
Lime & Shale	2998 to 3038
K.C. Lime	3038 to 3068
Lime	3068 to 3150
Conglomerate	3150 to 3166
Lime	3166 to 3193
Cherty Arbuckle	3193 to 3210 TD

PLUGGING
 FILE SEC 34 T11 N/SW
 BOOK PAGE 11 LINE 38