

15-167-20372-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Russell County, Sec. 34 Twp. 11 Rge. 15 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE NE NW  
Shields Oil Producers, Inc.

Lease Owner \_\_\_\_\_  
Lease Name Hagaman Well No. 1

Office Address Shields Bldg., Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed October 21, 1969

Application for plugging filed October 21, 1969

Application for plugging approved October 21, 1969

Plugging commenced October 21, 1969

Plugging completed October 21, 1969

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2,890 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	270'	Cmtd. w/185 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole w/ heavy mud  
Set bridge plug @ 480'  
Dump 40 sax cement on plug thru 4 1/2" drill pipe  
Set bridge plug @ 260'  
Dump 25 sax cement on plug thru 4 1/2" drill pipe  
Set bridge plug @ 40' w/ 1/4 sax hulls on plug  
Dump 10 sax cement on plug to cellar

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.  
Address Shields Bldg., Russell, Kansas

STATE OF Kansas COUNTY OF Russell, ss.  
R. J. Shields (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Shields  
Shields Bldg., Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of November, 1969

My commission expires May 26, 1981

Keith Phillips  
Notary Public.




Shields

15-167-20372-0000  
Russell, Kansas

WELL LOG

Operator: Shields Oil Producers, Inc.  
Well: Hagaman #1  
Commenced: October 16, 1969  
Completed: October 21, 1969  
Contractor: Shields Drilling Co., Inc.

Well Description: SE NE NW  
Sec. 34-11S-15W  
Russell County, Kansas



CASING RECORD

Size Run Pulled  
8 5/8" 270' Cmtd. w/ 185 sax

Elevation:  
Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations .....

Post rock	15'
Lime & shale	270'
Shale & Redbed	838'
Anhydrite	880'
Shale & shells	1,435'
Shale & lime	1,880'
Lime	2,070'
Lime & shale	2,615'
Lime	2,685'
Lime & shale	2,785'
Lime	2,890' RTD

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Notes