

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-167-05133-0001  
API NUMBER Drilled 1949

LEASE NAME Eulert

WELL NUMBER #8

1650 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 35 TWP. 11 RGE. 15 (E) or (W)

COUNTY Russell

Date Well Completed 1949

Plugging Commenced 6-8-98

Plugging Completed 6-8-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

LEASE OPERATOR American Warrior, Inc.

ADDRESS P.O. Box 399, Garden City, Kansas 67846

PHONE (316) 275-2963 OPERATORS LICENSE NO. 4058

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 8, 1998 (date)

by Herb Deines - District IV (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? No Logs in file

Producing Formation Lansing/KC Depth to Top 3006 Bottom 3221 T.O. 3290

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		.907	surf	8-5/8	907	NONE
		3314	surf	5-1/2	3314	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Mix 75 sks 60/40 poz 10% gel with 2 sks hulls, pump down 5-1/2" casing, followed with 17 sks gel, 65 sks cement tried onto 8-5/8" mix 105 sks cement with 2 sks hulls pressure to 400#, s.i. @ 200#, pumped 20 sks cement down 5-1/2" pressure to 600#, s.i. @ 500# job complete 3:00p.m. June 8th, 1998

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc.

STATE OF Kansas COUNTY OF Finney, ss.

Kevin Wiles, Sr.


(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 399, Garden City, KS 67846

SUBSCRIBED AND SWORN TO before me this 23<sup>rd</sup> day of June, 1998



My Commission Expires: Nov 4 1999

Debra Purcell  
Notary Public