

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-167-00357-0000

API NUMBER Drilled 10-28-49

LEASE NAME Eulert

WELL NUMBER 5

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 35 TWP. 11S RGE. 15 ~~XXXX~~(W)

COUNTY Russell

Date Well Completed 10-28-49

Plugging Commenced 10:00 a.m. 6-13-91

Plugging Completed 3:30 p.m. 6-13-91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Liedtke Operating Corporation

ADDRESS 370 17th Street, Suite 5020, Denver, CO 80202

PHONE# (303) 595-8405 OPERATORS LICENSE NO. 30385

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-13-91 (date)

by Don Butcher and Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing-Kansas City Depth to Top 3049' Bottom 3228' T.D. 3322'

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
 STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	115	None 115 sks
				4 1/2"	3316	None 225 sks

III 0-8-1991  
 07-08-91  
 CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Perforated 4 shots @ 920', 4 shots @ 440'; ran tubing to 3014'. Spotted 50 sks common 3% C.C., Pulled tubing to 900', spotted 40 sks 60-40 poz mix, 10% gel, Cement to surface. Pulled 900' tubing. Hooked onto 4 1/2". Pumped 335sks. 60-40 poz mix, 10% gel, 75 PSI. Hook up to 8-5/8". Pump 15 sks to surface, 60-40 poz mix, 10% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Chase Well Service, Inc. License No. 6123

Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Charles W. Steincamp


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles W. Steincamp

(Address) P. O. Box 355, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 1st day of July, 1991



Loneita Barry  
 Loneita Barry Notary Public